
Stech Engineers

Office Address Here

Tested Date:	2023-02-06 12:18:28	Test No:	87
Job Name :	test10samples	Batch ID:	test10samples
Specimen Name:	Rubber	Specmen Shape:	Rectangle
Test Type:	Tensile	Specmen Specs:	87
Party Name :	MRF	Motor Speed :	500
Guage Length(mm):	320	Report Date:	2023-02-06 12:20:22
Tested By :	Stech engineers testing machine		



Spec. No.	Thickness (cm)	Width (cm)	CS.Area (cm2)	Force at Peak (kgf)	E@Peak (cm)	% E@Peak	E@Break (cm)	%E@Break
1	0.26	0.61	0.1586	55.10	3.57	11.16	3.86	12.06
2	0.26	0.61	0.1586	63.30	2.45	7.66	3.85	12.03
3	0.26	0.61	0.1586	63.90	3.65	11.41	3.70	11.00
4	0.26	0.61	0.1586	65.60	4.28	13.38	4.92	15.38
5	0.26	0.61	0.1586	69.60	2.86	8.94	4.08	12.75
6	0.26	0.61	0.1586	80.60	4.17	13.03	5.16	16.12
7	0.26	0.61	0.1586	72.40	3.33	10.41	4.54	14.19
8	0.26	0.61	0.1586	66.10	3.01	9.41	4.35	13.59
9	0.26	0.61	0.1586	77.80	4.63	14.47	6.28	19.62
10	0.26	0.61	0.1586	72.10	4.48	14.00	5.68	17.75
AVG	0.26	0.61	0.1586	68.65	3.64	11.38	4.64	14.45
MAX	0.26	0.61	0.1586	80.60	4.63	14.47	6.28	19.62
MIN	0.26	0.61	0.1586	55.10	2.45	7.66	3.70	11.00

Spec.	TensileStrength	Mod@100%	Mod@200%	Mod@300%	l
No	(Kgf/Cm2)	(Kgf/Cm2)	(Kgf/Cm2)	(Kgf/Cm2)	

1	347.41	0.00	0.00	0.00
2	399.12	0.00	0.00	0.00
3	402.90	0.00	0.00	0.00
4	413.62	0.00	0.00	0.00
5	438.84	0.00	0.00	0.00
6	508.20	0.00	0.00	0.00
7	456.49	0.00	0.00	0.00
8	416.77	0.00	0.00	0.00
9	490.54	0.00	0.00	0.00
10	454.60	0.00	0.00	0.00
AVG	432.85	0.00	0.00	0.00
MAX	508.20	0.00	0.00	0.00
MIN	347.41	0.00	0.00	0.00

Remark	: None	
--------	--------	--

Remark : None
Authorised and Signed By :